



Haryana Government Gazette

Published by Authority

© Government of Haryana

No. 51-2019] CHANDIGARH, TUESDAY, DECEMBER 17, 2019 (AGRAHAYANA 26, 1941 SAKA)

PART-I

Notifications, Orders and Declarations by Haryana Government

HARYANA GOVERNMENT

PUBLIC WORKS DEPARTMENT
(Building and Roads Branch) Ambala Circle

Notification

The 6th December, 2019

No. SE/PWD (B&R)/Ambala/CZC/22.— Decision of the Direction Committee on Haryana P.W.D. Schedule of Rates 1988 (Second Edition) held on 08/11/2019.

The Direction committee discussed the Agenda and approved the following amendments in Haryana P.W.D. Schedule of rates 1988, Second Edition.

THESE AMENDMENTS WILL BE APPLICABLE FROM THE DATE OF GAZETTE NOTIFICATION.

Addenda and Corrigenda to the Haryana PWD Schedule of Rates 1988 (Second Edition)

A&C Slip No.34

Dated: 06/12/2019.

The meeting of Directions Committee of Haryana Schedule of Rates was held on 08/11/2019. The notification was got done *vide* **Notification No. SE/PWD (B&R) Ambala CZC/21 dated 11/11/2019 (published on 19/11/2019)**. While issuing amendment *vide* A&C Slip No.32 dated 11/11/2019 for Design Mix Concrete M-15, in the nomenclature of Item No.10.64; Reinforced Cement Concrete (RCC) had been approved in place of Plain Cement Concrete (PCC). Necessary amendments have been done and revised minutes have been issued / circulated. Accordingly, the following amendment is hereby made:

Existing item (A&C) Slip No.32 dated 11/11/2019 (Notification No. SE/PWD (B&R) Ambala CZC/21 dated 11/11/2019 (published on 19/11/2019):

Sr. No.	HSR Item	Description	Unit	Labour Rate	Through rate
1.	10.64	Providing & laying in position machine batched and machine mixed design mix M-15 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge in foundation and plinth. (Note: Cement content considered in this item is @ 240 kg./cum.).	Cum.	148	665.00

Now amended as under:

Sr. No.	HSR Item	Description	Unit	Labour Rate	Through rate
1.	10.64	Providing & laying in position machine batched and machine mixed design mix M-15 grade cement concrete for Plain cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering and finishing, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge in foundation and plinth. (Note: Cement content considered in this item is @ 240 kg./cum.).	Cum.	148	665.00

SANJIT KUMAR,
Convener, Central Zonal Committee,
Haryana PWD Schedule of Rates-cum-
Superintending Engineer, Ambala Circle, PWD (B&R), Ambala Cantt.